

WORK ITEM	DESCRIPTION (TYPE/SPECIFICATION)	SPECIAL NOTES	SIZE OR QUANTITY:
			SQUARE FEET/LINEAR
POOL	Latham - Corinthian 16 (40X16)	Access to backyard 15' plus	
RESHAPING THE DROP OFF BEHIND POOL PATIO	BACKFILL AND RESLOPE FROM BEHIND POOL PATIO Estimated amount (ton) with +15% compression 571.62 ton		
DRAINAGE SOLUTIONS	100' run from patio out to far corner of property line		
BACKFILLING AND COMPACTING	BACKFILL WITH COMPACT #57S WHERE POOL PATIO WILL BE INSTALLED - APPROX 2,000 SQ FT SURFACE X 4' (48") HIGH		
DEMOLITION/HAUL FROM SITE	DEMO AND HAUL 850 SQ FT OF CONCRETE		
PAVILLION STRUCTURE	BUILD 20' LONG X 12' WIDE WITH 4 POSTS , ROOF STRUCTURE, 4 ELECTRICAL OUTLETS, 1 FANS - COLOR AND FINISHES TBD		
KITCHEN ISLAND BUILD	12' LONG X 3' WIDE X 3' HIGH (TOTAL LINEAR FEET 30' LONG)		
KITCHEN ISLAND COMPONENTS	32" GRILL, DOUBLE DRAWERS, FRIDGE, TRASH CAN PULL OUT		
FIRE PIT BUILD (GAS)	5' WIDE DIAMETER X 18"/24" HIGH OUTSIDE DIMENSIONS - UNILOCK LINEO DIMENSIONAL BLOCK		
FIRE PIT COMPONENTS	STANDARD PALADINA COMPONENTS		
LED STRIP LIGHTING (KICHTEN ISLAND, FIRE PIT, PILLARS (2)	TOTAL LINEAR FEET FOR STRIP LIGHTING 70' PLUS 200' OF RUN TO POOL EQUIPMENT LOCATION		
HOT TUB (HARMONIC HOT TUB)	#H2810L Harmonic 2 Pump 8x10 Lounge - ELECTRIC LINE 60' LINEAR FEET		
POOL FEATURES - A	RAISED WALL +18" WITH 3 - 24" WIDE WATERFALL SHEER DESCENTS (WATERWAY NON LIT)		
POOL FEATURES - B	PILLARS 2'X2'X2' WITH FIRE BOWLS ON EACH (QUANTITY 2)		
RAISED PATIO BEHIND POOL - A	20'LONG X 9'WIDE X 18"HIGH WITH BLOCKHOUSE SINGLE BULLNOSE CAPS WITH UNILOCK LINEO DIMENSIONAL BLOCK		
STEPS FOR POOL PATIO (4 STEP DOWN TO POOL PATIO AND 12	LINCOLN WAY - BLOCKHOUSE - SCHENLEY STEPS 4' QUANTITY		16 STEPS
LAWN REPAIR	3,000 SQ FT OF LAWN REPAIR FOR PROPERTY		
MULCH BEDS REPAIR	1,000 SQ FT OF MULCH BED REPAIR ON PROPERTY		
STEPPER POOL PATIO (PAVER STEPPER)	PAVER STEPPERS 4'X4' - UNILOCK SKYLINE GRENADA WHITE 24" X 24"		2,100 SQ FT + % CUTS
STEPPER POOL PATIO (TURF FOR STEPPERS)	ARTIFICIAL TURF 8"		450 SQ FT + % CUTS
PAVER PATIO (FIELD)	UNILOCK BEACON HILL SMOOTH - GRANITE FUSION 3 PIECE RANDOM		980 SQ FT + % CUTS
PAVER PATIO (BORDER)	UNILOCK BEACON HILL SMOOTH DARK CHARCOAL 7 1/2" X 15" X 2 3/8"		400 SQ FT + % CUTS
REPAIR EXISTING WALL	REBUILD EXISTING WALL APPROXIMATELY 6' LONG X 6' HIGH (BLOCK TO MATCH EXISTING AS BEST AS POSSIBLE)		
LANDSCAPE PLANTING	NA		NA
LANDSCAPE LIGHTING	NA		NA